

Porta Cabin with Toilet

Combined working cabin and factory-plumbed wet zone. Six published sizes, 10x10 ft to 40x10 ft.

Field	Value
Product	Porta Cabin with Toilet
Canonical page	www.samanportable.com/product/porta-cabins/porta-cabin-with-toilet
Document number	SP-PC-WC-05-TS-R1
Issue date	14 August 2026
Specification source	SAMAN Porta Cabins 11 Products 6 Sizes Priced Revised, sheet 05 (Porta Cabin with Toilet, PC-WC-05); company facts from the SAMAN product SSOT, Fixed Facts L15, 08 Aug 2026
Price basis	Cost Estimation Input rate Rs 1,450 per sq ft at the 200 sq ft reference size, with the approved area-band adjustment. Status: Approved, direct Costing Sheet source.
Technical reviewer status	PENDING. This document is issued for buyer information and quotation input. It is not released for construction.

1. Published sizes and prices

Prices are ex-GST base specification prices. GST at 18 percent is shown separately. Interior fit-out, optional add-ons, transport, installation and foundations are excluded and quoted separately.

Size code	Published size	Area	Rate per sq ft	Price ex-GST	Incl. 18% GST
SZ-01	10x10x8.5 ft	100 sq ft	Rs 1,667.50	Rs 1,66,750	Rs 1,96,765
SZ-02	20x8x8.5 ft	160 sq ft	Rs 1,595.00	Rs 2,55,200	Rs 3,01,136
SZ-03	20x10x8.5 ft	200 sq ft	Rs 1,450.00	Rs 2,90,000	Rs 3,42,200
SZ-04	20x12x8.5 ft	240 sq ft	Rs 1,392.00	Rs 3,34,080	Rs 3,94,214
SZ-05	30x10x8.5 ft	300 sq ft	Rs 1,392.00	Rs 4,17,600	Rs 4,92,768
SZ-06	40x10x8.5 ft	400 sq ft	Rs 1,377.50	Rs 5,51,000	Rs 6,50,180

Base specification price. Customisations are quoted separately.

2. Size-related planning data

Published size	Occupancy basis	Site clearance required	Transport	Installation
10x10x8.5 ft	2 persons	14x14 ft level ground incl. working margin	Single truck or trailer; hydra unload	Same-day placement and hook-up
20x8x8.5 ft	See quotation	Confirmed with the approved layout drawing	Single truck or trailer; hydra unload	Confirmed at quotation
20x10x8.5 ft	4 persons	24x14 ft level ground incl. working margin	Single truck or trailer; hydra unload	Same-day placement and hook-up
20x12x8.5 ft	5 persons	24x16 ft level ground incl. working margin	Single truck or trailer; hydra unload	1 day placement; plug-in services
30x10x8.5 ft	7 persons	34x14 ft level ground incl. working margin	32-40 ft open trailer; crane unload	1 day placement; plug-in services

Published size	Occupancy basis	Site clearance required	Transport	Installation
40x10x8.5 ft	9 persons	44x14 ft level ground incl. working margin	40 ft open trailer (ODC check); crane unload	1 day placement; plug-in services

Occupancy figures are planning bases for layout, not statutory occupancy limits. The 20x8 ft size carries no published occupancy or clearance row in the approved source; both are confirmed at quotation.

3. Structure and envelope

Component	Specification
Bottom frame	100x50x3 mm MS C-channel primary base frame, ISI-standard or approved equivalent, fabricated as the load-bearing chassis
Bottom stiffeners	100x50 mm C-channels, 50x50 mm MS angles, 75x40 mm channels and approved square-pipe supports, typically coordinated at about 4 ft intervals to the final floor load and lifting design
Floor frame	MS base and cross-member grid supporting an 18 mm Bison or cement-fibre floor board fixed with approved self-tapping fasteners; spacing per the final drawing and design load
Top frame	50x50x1.6 mm MS square-pipe top perimeter frame of approved make or equivalent
Roof stiffeners	50x50x1.2 mm MS square-pipe roof stiffeners with 50x40, 40x40, 50x25 or 25x25 mm secondary members where required by span, ceiling support and drainage slope
Corner posts and walls	50x50x2 mm MS square-pipe corner and wall posts, or approved 60x60 mm MS-angle alternative, with reinforced door and window openings and an approximately 60 mm wall cavity
Exterior walls	1.2-1.6 mm corrugated MS sheet
Roof	1.4-1.6 mm corrugated MS sheet
Wall insulation	50 mm mineral wool where required
Roof insulation	75 mm glass or mineral wool
Lifting and handling	Engineered lifting and support points for each transportable module. Move the completed module only to the approved lifting, support and transport drawing.
Welding and fabrication	Qualified welded or bolted structural connections to approved shop drawings; deburred safe edges, dimensional inspection, protected cut edges; panels close only after frame inspection
External finish	Project-selected colour and compatible coating system, confirmed in the approved finish schedule
Fasteners and sealing	Corrosion-compatible mechanical fasteners, EPDM, butyl or approved sealants and flashings at panel joints, corners, roof laps and penetrations. No unsealed field cuts are accepted.

4. Wet zone, interior and services

Component	Specification
Interior walls	10-12 mm fibre-cement board with moisture-tolerant lining and an approved hygienic finish in wet zones
Ceiling	8-10 mm fibre-cement or washable PVC
Floor base	18-24 mm cement board with waterproof membrane
Floor finish	2.5-3 mm anti-skid safety vinyl with sealed joints
Doors	Waterproof flush doors with corrosion-resistant hardware and privacy fittings

Component	Specification
Windows and openings	Frosted aluminium ventilators and windows
Grills and mesh	Security grill, mosquito mesh, guard or louver provided only where the approved opening schedule and intended use require it
Plumbing and sanitary	EWC or Indian WC, urinals, washbasins, flushing, CPVC supply, UPVC waste, traps and floor drains according to the approved layout
Layout	Separated toilet, urinal and washbasin zones according to the selected seat count
Ventilation	Mandatory mechanical exhaust with natural ventilators
Electrical wiring	Concealed or protected copper wiring, typically 1.5 sq mm for lighting, 2.5 sq mm for sockets and 4 sq mm for higher-load or AC circuits, subject to the final load schedule and approved electrical drawing
Electrical protection	Distribution board with MCB and RCCB protection, earthing, and segregation of lighting, socket, wet-area and AC circuits per the approved electrical drawing
Electrical fittings	LED lights, modular switches, 6A and 16A sockets, fan points and AC provision coordinated with the approved layout. Final quantities and equipment loads are quotation-specific.
Painting and coating	Corrosion protection matched to substrate and exposure: prepared MS receives the approved primer and topcoat system; galvanized or coated steel receives compatible cut-edge and damage repair plus coating touch-up where specified
Quality checks	Pre-dispatch QA covers dimensions, member and panel identification, connections, coating, roof drainage, weather sealing, doors, windows, electrical continuity and functional checks. Specialist performance certificates are verified where the product requires them.

5. Scope: standard, optional, custom and excluded

Scope	Items
Standard	MS structure and corrugated shell; wet-zone lining and waterproofed floor; factory plumbing with fixtures to the approved layout; mechanical exhaust and ventilators; waterproof flush doors with privacy fittings; electrical wiring with protected circuits to the approved drawing
Optional	Air-conditioning provision; additional protected openings with grills or mesh where the schedule requires; finishing warranty extension to 2 years, confirmed at quotation
Custom	Seat count and zone layout; fixture selection, EWC or Indian WC; colour and coating system; opening positions to suit placement
Excluded	Interior fit-out and furniture; transport and installation; foundations and site civil work; water storage and onward drainage; statutory approvals at the site

6. Site interface

Fitted at the factory	Arranged by the site
CPVC supply runs to every fixture	Water supply line up to the cabin connection
UPVC waste piping, traps and floor drains	Onward drainage to a septic tank or sewer point
WC, urinal and washbasin fixtures with flushing	Water storage and any pressure boosting
Mechanical exhaust and frosted ventilators	Power supply to the cabin distribution board
Waterproofed wet-zone floor and lining	Level base and placement access

7. Quotation inputs required from the buyer

- Size or floor area from the published ladder in section 1.
- Seat count and fixture preference: EWC or Indian WC, urinals, washbasins.
- Working-room use, if a dry room is required alongside the wet zone.
- Site district or PIN code, for the distance-band freight calculation.
- Existing water point, drainage route and power connection at the site.
- Any optional or custom scope from section 5.

8. Commercial and company facts

Item	Value
Delivery	7-21 working days from order confirmation. Fixed-price quotation within 48 hours of a complete enquiry.
Freight	Free within Bangalore city and Delhi NCR (Ghaziabad, Gurugram, Faridabad, Noida, Greater Noida). Other destinations follow the approved distance-band freight ladder. Freight is tentative until the delivery location and order are confirmed and can vary with route and vehicle return.
Warranty	5-year structural warranty and 1-year finishing warranty as standard; finishing warranty extendable to 2 years on request, confirmed at quotation.
Service life	20-25 years under proper use and maintenance. This is an expected service life, not a warranty period.
GST	18 percent. Prices ex-GST are primary. HSN 9406 for prefabricated buildings.
Manufacturer	SAMAN POS India Private Limited, brand SAMAN Portable. Manufacturing units at Bengaluru and Greater Noida. Manufacturer, not reseller.
Certifications	ISO 9001:2015; ISO 14001:2015; ISO 45001:2018; NSIC SPRS enlisted; Udyam registered; DPIIT Startup India; GST registered.
Contact	Bengaluru: +91 88616 22859, +91 80886 85440, sales@samanportable.com. Greater Noida: +91 87960 39938, +91 97089 89937, ncr@samanportable.com. Monday to Saturday, 09:00-20:00 IST.

9. Status of this document

This specification is issued for buyer information and quotation input. Final engineering, bill of materials and drawings remain controlled documents. Quantities, openings and services scale with the approved drawing for the selected size. Where a value is stated as a range, the final value is confirmed in the approved drawing and quotation. **Not for construction unless approved.**