

Modern Office Cabin - Technical Specifications & Price List

Canonical URL: <https://www.samanportable.com/product/portable-office/modern-office-cabin>

Sizes & Prices

| SIZE     | AREA (SQ FT) | EX-GST       | INCL. 18% GST |
|----------|--------------|--------------|---------------|
| 10×10 ft | 100          | INR 1,55,900 | INR 1,83,962  |
| 20×8 ft  | 160          | INR 2,49,440 | INR 2,94,339  |
| 20×10 ft | 200          | INR 2,83,600 | INR 3,34,648  |
| 20×12 ft | 240          | INR 3,26,640 | INR 3,85,435  |
| 30×10 ft | 300          | INR 4,08,300 | INR 4,81,794  |
| 40×8 ft  | 320          | INR 4,26,240 | INR 5,02,963  |
| 40×10 ft | 400          | INR 5,32,800 | INR 6,28,704  |
| 20×20 ft | 400          | INR 5,32,800 | INR 6,28,704  |
| 40×12 ft | 480          | INR 6,25,920 | INR 7,38,586  |

Prices shown are the published page values. Ex-GST and incl. 18% GST amounts are listed separately.

Technical Specifications

Steel Structure

| COMPONENT             | DETAIL                                                                                                                                                                                   |
|-----------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Bottom frame          | 100×50×3 mm MS C-channel primary base frame, ISI-standard or approved equivalent, fabricated as the load-bearing chassis.                                                                |
| Bottom stiffeners     | 100×50 mm C-channels, 50×50 mm MS angles, 75×40 mm channels and approved square-pipe supports, typically coordinated at about 4 ft intervals to the final floor load and lifting design. |
| Floor frame           | MS base and cross-member grid supporting an 18 mm Bison/cement-fibre floor board fixed with approved self-tapping fasteners; spacing follows the final drawing and design load.          |
| Top frame             | 50×50×1.6 mm MS square-pipe top perimeter frame of approved make or equivalent.                                                                                                          |
| Roof stiffeners       | 50×50×1.2 mm MS square-pipe roof stiffeners with 50×40, 40×40, 50×25 or 25×25 mm secondary members where required by span, ceiling support and drainage slope.                           |
| Corner posts / walls  | 50×50×2 mm MS square-pipe corner and wall posts or approved 60×60 mm MS-angle alternative, with reinforced door and window openings and an approximately 60 mm wall cavity.              |
| Lifting / handling    | Designed MS lifting hooks or lugs matched to the completed unit weight; handle only by the approved lifting and support-point drawing.                                                   |
| Welding & fabrication | Welded MS fabrication with cleaned joints, safe edges, dimensional inspection and coating touch-up before panel closure and dispatch.                                                    |

Walls, Roof, Floor & Insulation

| COMPONENT       | DETAIL                                                     |
|-----------------|------------------------------------------------------------|
| Exterior walls  | 1.2 mm specially corrugated MS sheet                       |
| Roof            | 1.4 mm corrugated MS sheet                                 |
| Interior walls  | 8 mm pre-laminated MDF board with aluminium joint sections |
| Ceiling         | 8 mm pre-laminated MDF ceiling                             |
| Floor base      | 18 mm Bison panel                                          |
| Floor finish    | 1.3 mm vinyl flooring                                      |
| Wall insulation | 25 mm glass wool or 12 mm heatlon                          |
| Roof insulation | 50 mm glass wool, nominal density 42 kg/m³                 |

| COMPONENT                    | DETAIL                                                                                                                          |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------|
| Decorative / external finish | Standard anti-rust enamel exterior finish in an approved colour combination.                                                    |
| Fasteners & sealing          | Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it. |

Doors, Windows, Electrical & Services

| COMPONENT                 | DETAIL                                                                                                                                                                                                                                                                                    |
|---------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Main door / service door  | 7×3 ft externally opening MS-framed door using 30×30 mm MS tubular sections                                                                                                                                                                                                               |
| Windows / service opening | Two-track powder-coated aluminium sliding windows with 4 mm glass                                                                                                                                                                                                                         |
| Grills / mosquito mesh    | Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.                                                                                                                                                           |
| Electrical wiring         | Concealed PVC-insulated copper wiring, typically 1.5 sq.mm lighting, 2.5 sq.mm sockets and 4 sq.mm higher-load or AC circuits, subject to the final load schedule.                                                                                                                        |
| Electrical protection     | Distribution board with MCB/RCCB protection, earthing and segregation of lighting, socket, wet-area and AC circuits according to the approved electrical drawing.                                                                                                                         |
| Electrical fittings       | Porta Cabin electrical package adapted to the approved office load schedule with workstation sockets, data/UPS routes, lighting, fan points and AC provision; circuit quantities are quotation-controlled.                                                                                |
| Ventilation / AC          | Cross-ventilation and office-comfort provision coordinated to occupancy, glazing and AC selection without changing the underlying Porta Cabin construction.                                                                                                                               |
| Plumbing / sanitary       | Not included unless shown in the approved scope.                                                                                                                                                                                                                                          |
| Layout / configuration    | Office configuration on the Porta Cabin material baseline: Premium laminate, larger tinted windows, SPC or LVT flooring and higher insulation create the modern specification. Final workstation count, partitions, furniture clearances and circulation follow the approved office plan. |
| Painting / coating        | One red-oxide primer coat followed by two compatible anti-rust enamel coats on prepared MS surfaces; project exposure may require an upgraded coating system.                                                                                                                             |
| Quality checks            | Pre-dispatch checks cover dimensions, member and sheet identification, welds, coating, roof drainage, weather sealing, doors, windows, electrical continuity and functional operation.                                                                                                    |
| Warranty                  | 5-year structural warranty and 1-year finishing warranty as standard; finishing warranty extendable to 2 years on request, confirmed at quotation.                                                                                                                                        |

Commercial & Company Facts

Warranty: 5-year structural warranty and 1-year finishing warranty as standard; finishing warranty extendable to 2 years on request, confirmed at quotation.

Delivery: Delivery in 7 to 21 working days

Quotation: Fixed-price quote within 48 hours

Certifications: ISO 9001:2015 (E20250218645); ISO 14001:2015 (E20250218646); ISO 45001:2018 (E20250218647); NSIC SPRS (NSIC/GP/BAN/2024/0055207); Udyam UDYAM-KR-03-0172770; ZED Bronze; DPIIT Startup India (DIPP56005); GST registered.

Bengaluru Unit 1 South: +91 88616 22859 | +91 80886 85440 | sales@samanportable.com

Greater Noida Unit 2 North: +91 87960 39938 | +91 97089 89937 | ncr@samanportable.com

Generated: 30 July 2026