

TECHNICAL REFERENCE

Portable Office Cabin

Technical Specification

<https://www.samanportable.com/product/portable-office>

Six published sizes and prices

SIZE	DIMENSIONS	AREA	RECOMMENDED OCCUPANCY	EX-GST	INCL. 18% GST
10×10 ft	10×10×8.5 ft	100 sq ft	Recommended occupancy 2–3 people	INR 1,48,500	INR 1,75,230
20×8 ft	20×8×8.5 ft	160 sq ft	Recommended occupancy 3–4 people	INR 2,37,600	INR 2,80,368
20×10 ft	20×10×8.5 ft	200 sq ft	Recommended occupancy 4–6 people	INR 2,70,000	INR 3,18,600
20×12 ft	20×12×8.5 ft	240 sq ft	Recommended occupancy 5–7 people	INR 3,11,040	INR 3,67,027
30×10 ft	30×10×8.5 ft	300 sq ft	Recommended occupancy 6–8 people	INR 3,88,800	INR 4,58,784
40×10 ft	40×10×8.5 ft	400 sq ft	Recommended occupancy 8–10 people	INR 5,07,600	INR 5,98,968

GST 18% | HSN 9406 | Published prices use the approved current ladder.

The six published standard sizes are regularly stocked. Custom sizes are made to order and priced in the written quotation.

Written quotation within 48 hours. Delivery in 7–21 working days. Free delivery within Bangalore city and Delhi NCR; freight outside those zones is quoted separately.

Five-year structural warranty and one-year finishing warranty, subject to the written warranty and quotation terms.

02 Steel Structure

Common platform: MS structural frame with insulated office construction, factory-fitted electricals, quotation within 48 hours, and delivery in 7 to 21 working days.

COMPONENT	APPROVED CURRENT REQUIREMENT
Bottom frame	100×50×3 mm MS C-channel primary base frame, ISI-standard or approved equivalent, fabricated as the load-bearing chassis.
Bottom stiffeners	100×50 mm C-channels, 50×50 mm MS angles, 75×40 mm channels and approved square-pipe supports, typically coordinated at about 4 ft intervals to the final floor load and lifting design.
Floor frame	MS base and cross-member grid supporting an 18 mm Bison/cement-fibre floor board fixed with approved self-tapping fasteners; spacing follows the final drawing and design load.
Top frame	50×50×1.6 mm MS square-pipe top perimeter frame of approved make or equivalent.
Roof stiffeners	50×50×1.2 mm MS square-pipe roof stiffeners with 50×40, 40×40, 50×25 or 25×25 mm secondary members where required by span, ceiling support and drainage slope.
Corner posts / walls	50×50×2 mm MS square-pipe corner and wall posts or approved 60×60 mm MS-angle alternative, with reinforced door and window openings and an approximately 60 mm wall cavity.
Lifting / handling	Designed MS lifting hooks or lugs matched to the completed unit weight; handle only by the approved lifting and support-point drawing.
Welding & fabrication	Welded MS fabrication with cleaned joints, safe edges, dimensional inspection and coating touch-up before panel closure and dispatch.

03 Walls, Roof, Floor & Insulation

Common platform: MS structural frame with insulated office construction, factory-fitted electricals, quotation within 48 hours, and delivery in 7 to 21 working days.

COMPONENT	APPROVED CURRENT REQUIREMENT
Exterior walls	1.2 mm specially corrugated MS sheet
Roof	1.4 mm corrugated MS sheet
Interior walls	8 mm pre-laminated MDF board with aluminium joint sections
Ceiling	8 mm pre-laminated MDF ceiling
Floor base	18 mm Bison panel
Floor finish	1.3 mm vinyl flooring
Wall insulation	25 mm glass wool or 12 mm heatlon
Roof insulation	50 mm glass wool, nominal density 42 kg/m ³
Decorative / external finish	Standard anti-rust enamel exterior finish in an approved colour combination.
Fasteners & sealing	Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.

04 Doors, Windows, Electrical & Services

Common platform: MS structural frame with insulated office construction, factory-fitted electricals, quotation within 48 hours, and delivery in 7 to 21 working days.

COMPONENT	APPROVED CURRENT REQUIREMENT
Main door / service door	7×3 ft externally opening MS-framed door using 30×30 mm MS tubular sections
Windows / service opening	Two-track powder-coated aluminium sliding windows with 4 mm glass
Grills / mosquito mesh	Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.
Electrical wiring	Concealed PVC-insulated copper wiring, typically 1.5 sq.mm lighting, 2.5 sq.mm sockets and 4 sq.mm higher-load or AC circuits, subject to the final load schedule.
Electrical protection	Distribution board with MCB/RCCB protection, earthing and segregation of lighting, socket, wet-area and AC circuits according to the approved electrical drawing.
Electrical fittings	Porta Cabin electrical package adapted to the approved office load schedule with workstation sockets, data/UPS routes, lighting, fan points and AC provision; circuit quantities are quotation-controlled.
Ventilation / AC	Cross-ventilation and office-comfort provision coordinated to occupancy, glazing and AC selection without changing the underlying Porta Cabin construction.
Plumbing / sanitary	Not included unless shown in the approved scope.
Layout / configuration	Six-size Portable Office Cabin range on the approved shared structural platform; final workstation positions, partitions and circulation follow the written quotation.
Painting / coating	One red-oxide primer coat followed by two compatible anti-rust enamel coats on prepared MS surfaces; project exposure may require an upgraded coating system.
Quality checks	Pre-dispatch checks cover dimensions, member and sheet identification, welds, coating, roof drainage, weather sealing, doors, windows, electrical continuity and functional operation.
Warranty	Five-year structural warranty and one-year finishing warranty, subject to the written warranty and quotation terms.

05 Approved inclusions and company evidence

Factory-built MS Portable Office Cabin supplied as one complete unit across six standard sizes from 10x10 to 40x10 ft, all at an approved 8.5 ft height. The detailed structural frame, cladding, insulation, flooring and electrical package follow the approved current specification.

Approved current inclusions

The three specification tables in this document are the maintained inclusion source for the structural frame, wall/roof/floor build, insulation, openings, electrical services, finishes, quality checks and warranty.

Verified company credentials

SAMAN POS India Private Limited

ISO 9001:2015 quality management certificate, subject to the certificate conditions; GST registrations for Karnataka and Uttar Pradesh; Udyam registration; DPIIT Startup India recognition; and NSIC Government Purchase enlistment.

Zonal contacts

South India: +91 88616 22859

North India: +91 87960 39938

www.samanportable.com

Document version: PO-FAM-01B / 01 Sep 2026