

TECHNICAL REFERENCE

Readymade Office Cabin

Technical Specification

<https://www.samanportable.com/product/portable-office/readymade-office-cabin>

Six published sizes and prices

SIZE	DIMENSIONS	AREA	RECOMMENDED OCCUPANCY	EX-GST	INCL. 18% GST
10×10 ft	10×10×8.5 ft	100 sq ft	Recommended occupancy 2–3 people	INR 1,41,100	INR 1,66,498
20×8 ft	20×8×8.5 ft	160 sq ft	Recommended occupancy 3–4 people	INR 2,25,760	INR 2,66,397
20×10 ft	20×10×8.5 ft	200 sq ft	Recommended occupancy 4–6 people	INR 2,56,400	INR 3,02,552
20×12 ft	20×12×8.5 ft	240 sq ft	Recommended occupancy 5–7 people	INR 2,95,440	INR 3,48,619
30×10 ft	30×10×8.5 ft	300 sq ft	Recommended occupancy 6–8 people	INR 3,69,300	INR 4,35,774
40×10 ft	40×10×8.5 ft	400 sq ft	Recommended occupancy 8–10 people	INR 4,82,400	INR 5,69,232

GST 18% | HSN 9406 | Published prices use the approved current ladder.

Availability is confirmed with the written quotation.

Written quotation within 48 hours. Delivery in 7–21 working days. Free delivery within Bangalore city and Delhi NCR; freight outside those zones is quoted separately.

Five-year structural warranty and one-year finishing warranty, subject to the written warranty and quotation terms.

02 Steel Structure

Common platform: MS structural frame with insulated office construction, factory-fitted electricals, quotation within 48 hours, and delivery in 7 to 21 working days.

COMPONENT	APPROVED CURRENT REQUIREMENT
Bottom frame	100×50×3 mm MS C-channel primary base frame fabricated to the approved fixed drawing.
Bottom stiffeners	100×50 mm C-channels with 50×50 mm MS angles on the approved fixed grid.
Floor frame	MS base and cross-member grid supporting an 18 mm Bison/cement-fibre floor board fixed with approved self-tapping fasteners; spacing follows the final drawing and design load.
Top frame	50×50×1.6 mm MS square-pipe top perimeter frame to the approved fixed drawing.
Roof stiffeners	50×50×1.2 mm MS square-pipe roof stiffeners at the approved fixed spacing.
Corner posts / walls	50×50×2 mm MS square-pipe corner and wall posts in the approved fixed positions.
Lifting / handling	Designed MS lifting hooks or lugs matched to the completed unit weight; handle only by the approved lifting and support-point drawing.
Welding & fabrication	Welded MS fabrication with cleaned joints, safe edges, dimensional inspection and coating touch-up before panel closure and dispatch.

03 Walls, Roof, Floor & Insulation

Common platform: MS structural frame with insulated office construction, factory-fitted electricals, quotation within 48 hours, and delivery in 7 to 21 working days.

COMPONENT	APPROVED CURRENT REQUIREMENT
Exterior walls	1.2 mm specially corrugated MS sheet
Roof	1.4 mm corrugated MS sheet
Interior walls	8 mm pre-laminated MDF board with aluminium joint sections
Ceiling	8 mm pre-laminated MDF ceiling
Floor base	18 mm Bison panel
Floor finish	1.3 mm vinyl flooring
Wall insulation	12 mm heatlon in the approved fixed inclusion list.
Roof insulation	50 mm glass wool, nominal density 42 kg/m ³
Decorative / external finish	Standard anti-rust enamel exterior finish in an approved colour combination.
Fasteners & sealing	Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.

04 Doors, Windows, Electrical & Services

Common platform: MS structural frame with insulated office construction, factory-fitted electricals, quotation within 48 hours, and delivery in 7 to 21 working days.

COMPONENT	APPROVED CURRENT REQUIREMENT
Main door / service door	7×3 ft externally opening MS-framed door using 30×30 mm MS tubular sections in the approved fixed position.
Windows / service opening	Two-track powder-coated aluminium sliding windows with 4 mm glass in the approved fixed openings.
Grills / mosquito mesh	Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.
Electrical wiring	Concealed PVC-insulated copper wiring, typically 1.5 sq.mm lighting, 2.5 sq.mm sockets and 4 sq.mm higher-load or AC circuits, subject to the final load schedule.
Electrical protection	Distribution board with MCB/RCCB protection, earthing and segregation of lighting, socket, wet-area and AC circuits according to the approved electrical drawing.
Electrical fittings	Preplanned electrical points from the approved fixed inclusion list, terminated and tested in the factory.
Ventilation / AC	Cross-ventilation and AC provision coordinated to the approved fixed layout.
Plumbing / sanitary	Not included unless shown in the approved scope.
Layout / configuration	Approved fixed-inclusion configuration with predictable openings and preplanned electrical points; other requirements are reviewed and priced separately in the written quotation.
Painting / coating	One red-oxide primer coat followed by two compatible anti-rust enamel coats on prepared MS surfaces; project exposure may require an upgraded coating system.
Quality checks	Pre-dispatch checks cover dimensions, member and sheet identification, welds, coating, roof drainage, weather sealing, doors, windows, electrical continuity and functional operation.
Warranty	Five-year structural warranty and one-year finishing warranty, subject to the written warranty and quotation terms.

05 Approved inclusions and company evidence

Factory-finished Readymade Office Cabin built to one approved fixed inclusion list across six published sizes. Lighting circuits, fan outlets, socket pairs and the switchboard are positioned and tested in the factory. Availability is confirmed with the written quotation.

Approved current inclusions

The three specification tables in this document are the maintained inclusion source for the structural frame, wall/roof/floor build, insulation, openings, electrical services, finishes, quality checks and warranty.

Verified company credentials

SAMAN POS India Private Limited

ISO 9001:2015 quality management certificate, subject to the certificate conditions; GST registrations for Karnataka and Uttar Pradesh; Udyam registration; DPIIT Startup India recognition; and NSIC Government Purchase enlistment.

Zonal contacts

South India: +91 88616 22859

North India: +91 87960 39938

www.samanportable.com

Document version: PO-FAM-01B / 01 Sep 2026