

Container Cafe - Technical Specifications and Price List

Canonical URL: <https://www.samanportable.com/product/container-cafe>

Six approved sizes and prices

SIZE	AREA (SQ FT)	RATE EX-GST	EX-GST	INCL. 18% GST
10x10x8.5 ft	100	INR 2,035/sq ft	INR 2,03,500	INR 2,40,130
20x8x8.5 ft	160	INR 2,035/sq ft	INR 3,25,600	INR 3,84,208
20x10x8.5 ft	200	INR 1,850/sq ft	INR 3,70,000	INR 4,36,600
20x12x8.5 ft	240	INR 1,776/sq ft	INR 4,26,240	INR 5,02,963
30x10x8.5 ft	300	INR 1,776/sq ft	INR 5,32,800	INR 6,28,704
40x10x8.5 ft	400	INR 1,739/sq ft	INR 6,95,600	INR 8,20,808

Base specification price - customisations quoted separately. Ex-factory, ex-GST.

Steel Structure

COMPONENT	DETAIL
Bottom frame	125×75×4 mm or 150×75×5 mm MS C-channel
Bottom stiffeners	100×50×3–4 mm channels with counter and equipment reinforcement
Floor frame	80×40×3 mm or 100×50×3 mm primary floor supports
Top frame	80×40×3 mm MS top perimeter
Roof stiffeners	60×40×2.5 mm roof members with exhaust and signage supports
Corner posts / walls	60×60×3 mm posts with façade and counter framing
Lifting / handling	Designed MS lifting hooks or lugs matched to the completed unit weight; handle only by the approved lifting and support-point drawing.
Welding & fabrication	Welded MS fabrication with cleaned joints, safe edges, dimensional inspection and coating touch-up before panel closure and dispatch.

Walls, Roof, Floor & Insulation

COMPONENT	DETAIL
Exterior walls	1.2–1.6 mm corrugated MS structural sheet with decorative over-cladding
Roof	1.4–1.6 mm corrugated MS sheet
Interior walls	8–10 mm fibre-cement board, HPL or stainless-steel lining in food-service zones
Ceiling	Washable fibre-cement, ACP, PVC or metal-liner ceiling
Floor base	18–24 mm cement fibre board with waterproof treatment
Floor finish	Anti-skid tile, 3–4 mm PU/epoxy or 2.5 mm safety vinyl
Wall insulation	50–75 mm mineral wool
Roof insulation	75–100 mm mineral wool
Decorative / external finish	4 mm ACP, 6–8 mm HPL, WPC or wooden-finish metal over-cladding above the mandatory corrugated MS structural shell.
Fasteners & sealing	Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.

Doors, Windows, Electrical & Services

COMPONENT	DETAIL
Main door / service door	Staff/customer door plus lockable service counter or shutter.
Windows / service opening	Large aluminium service glazing with lockable counter opening.
Grills / mosquito mesh	Security grill, insect mesh, guard, louver or protection selected only where the approved use and opening schedule requires it.
Electrical wiring	Concealed PVC-insulated copper wiring, typically 1.5 sq.mm lighting, 2.5 sq.mm sockets and 4 sq.mm higher-load or AC circuits, subject to the final load schedule.
Electrical protection	Distribution board with MCB/RCCB protection, earthing and segregation of lighting, socket, wet-area and AC circuits according to the approved electrical drawing.

COMPONENT	DETAIL
Electrical fittings	LED lighting, signage supply, multiple 6A/16A appliance sockets, dedicated equipment circuits and DB/MCB protection.
Ventilation / AC	Exhaust-hood/duct provision, fresh-air opening and optional AC for the customer zone.
Plumbing / sanitary	Sink/handwash, CPVC water supply, UPVC waste and equipment connection points according to layout.
Layout / configuration	Front service counter with separate staff preparation and storage zones.
Painting / coating	One red-oxide primer coat followed by two compatible anti-rust enamel coats on prepared MS surfaces; project exposure may require an upgraded coating system.
Quality checks	Pre-dispatch checks cover dimensions, member and sheet identification, welds, coating, roof drainage, weather sealing, doors, windows, electrical continuity and functional operation.

Contacts

South: +91 88616 22859 | sales@samanportable.com

North: +91 87960 39938 | ncr@samanportable.com

Generated: 05 September 2026